

This Bulletin contains changes in and/or additions to work in the original drawings and for this project. All changes contained herein and on the accompanying drawings with revision date of this addendum shall become part of the contract drawings and shall conform to the basic specifications unless otherwise noted.

Drawings Changes

1. A1.1 In lieu of sheet revised date 11/20/07 substitute sheet dated 2/17/09 The primary change is relocating the 1 hr wall around the Lobby / Breakfast and separating it with a 1 hr rated wall between the Offices Meeting, Exercise and Pantry
 - a. In lieu of doors specified substitute a rated doors at: 9 to Pool Vestibule, 10 to Exercise, 19 to Night Window, 26 to Meeting.
 - b. Add rated door 23b at Mech. Closets located in Pantry Storage and at East end of Corridor.
 - c. At bath exhaust pipe substitute a rated floor UL FC100
2. A1.2 In lieu of sheet revised date 8/24/07 and Bulletin 1 dated 4/11/08 substitute sheet dated 2/17/09. The primary change is adding 1 hr rated walls around Mech. Closets located at each end of Corridors and installing rated door 23b to each.
 - a. At bath exhaust pipe substitute a rated floor UL FC7029.
3. A3.1 In lieu of sheet date 8/24/07 substitute sheet dated 2/17/09. The primary change is changing Brick Veneer to Field Stone and changing Porte Cochere roof to a hip and adding a Cupola.
4. A4.5 Added Sheet Includes:
 - a. details 1-3 hold down details at LVL beams supporting Roof trusses at north side of Corridor.
 - b. details 4-6 & 18 changes at Porte Cochere and adding Cupola.
 - c. details 7-10 are Tie Down for gang trusses supporting roof trusses at each gable.
 - d. details 11-17 are Tie Down for Pool Clerestory.
 - e. Details 20 & 21 are additional hold downs at LVL beam.
5. S1.1 In lieu of sheets with revision date 11/20/07 substitute sheet dated 2-17-09. The primary change is adding additional slab at Pool and changing Porte Cochere from eight (8) columns with gable to 4 columns, a hip roof and cupola.
6. S1.5 Added Sheet includes.
 - a. Main Roof Truss Plan –indicating shear walls, additional hold downs at shear walls and LVL beams on north side of Corridor supporting roof truss, Porte Cochere Steel Beams, Knee Brace.
 - b. Tower Roof Truss Plan indicating shear walls and additional hold downs at shear walls
 - c. Porte Cochere Roof with Cupola.

7. M1.1 In lieu of sheets revised date 8/24/07 and Bulletin 1 dated 4/11/08 substitute sheet dated 2/17/09. The primary change is adding fire dampers at rated walls where ducts penetrate and access panels to fire dampers which are not near a register.
 - a. At Corridor and Meeting Rm- In Lieu of VPTAC units specified install split systems A18 AHU and condensing unit. See detail 3, sheet M1.2
 - b. Add a EF-2 at Pantry switched near convection oven, extend exhaust duct low to roof over Exercise Rm. provide roof cowlin and backdraft.

8. M1.2 In lieu of sheets revised date 8/24/07 and Bulletin 1 dated 4/11/08 substitute sheet dated 2/17/09. The primary change at Corridors- In Lieu of VPTAC units specified install split systems A18 AHU and condensing unit. See detail 3, sheet M1.2